



**NOTES:**

1. FINAL 28 DAY CONCRETE CURE TO TO 4500 PSI.
2. #6 BARE COPPER GROUND WIRE AND 5/8" X 8' CW GROUND ROD TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.

ORG. BY MRC  
07/05/07  
APPROVED

**PRECAST CONCRETE 30' STREETLIGHT BASE**

**GROTON UTILITIES**

CONSTRUCTION STANDARD

**E 12.405**

-

This page left intentionally blank.